
A Guide to Field Instrumentation in Geotechnics

Principles, installation and reading

Richard Bassett

Contents

<i>List of figures and tables</i>	ix
<i>Foreword</i>	xvii
<i>Acknowledgements</i>	xviii
Introduction	1
1 The general philosophy of geotechnical instrumentation	2
<i>Philosophy</i>	2
<i>Levels of instrumentation</i>	3
<i>Rates of change</i>	3
<i>Types of monitoring</i>	3
2 Basic soil mechanics and pore pressures	6
<i>Soils as a simplified model</i>	6
<i>Pore pressure measuring instruments</i>	14
<i>Types of piezometer</i>	14
<i>Removable piezometers</i>	20
<i>Using the simplified model to interpret pore water pressure responses</i>	20
<i>Cuttings</i>	26
<i>Embankments</i>	28
<i>Tunnels</i>	30
3 Displacements and global deformations	37
<i>General</i>	37
<i>Strains and deformations</i>	38
<i>Vertical displacements within structures and soils</i>	38
<i>Hydraulics</i>	39
<i>Piezometer settlement cells</i>	40

Displacement of structures	43
Incorrect use of electrolevel beam systems	46
Horizontal displacements in structures	51
Vertical displacements in soils by mechanical means	51
Micrometer settlement measurements (the rod extensometer)	53
Magnetic plates and reed switch sensors (the magnetic extensometer)	55
Deformations in soils using inclinometers and hydrostatic profile gauges	57
Inclinometers: the technician	60
Inclination and the reading unit	61
The inclinometer body	62
Minimising instrument zero and small casing errors	66
Fundamentals of inclinometer installation	68
The reference casing	69
The borehole	71
The installation	73
Installation procedure	74
Theoretical concepts behind borehole grouting	74
Subsequent soil displacement	76
In-place inclinometers	78
Horizontal profile gauges using an inclinometer probe or IPI units	80
Interpretation	80
Data reduction	82
Advanced uses of combined horizontal and vertical displacements	88
The Mohr circle of strain	89
4 Vibrating wire instruments and localised measurement of strains	100
Basic mechanics of vibrating wire instruments and linear strain measurement	100
Real design considerations	101
Load cells and embedded strain gauges using the reaction beam as the strain control	106
Load and stresses	109
Analysis of stresses to provide full stress analysis	109
The interpretation of vibrating wire instruments	110
Assessment and interpretation of vibrating wire data	110
Strains	111
Data interpretation	113

	Pore pressure change	116
	Interpreting other vibrating wire instruments, load cells and crackmeters	117
	Cracks and damage measurement	117
	Crack monitoring instruments	121
5	Survey techniques	126
	Total station monitoring	126
	Use of automatic total stations	126
	Prisms	133
	Mounting systems	137
	Limitations in tunnels	137
	Advanced optical systems	140
6	Specialist instruments	144
	The Bassett convergence system	144
	The geometric principles of a bar/cam unit	144
	Geometry of the beam/cam system	147
	The BCS field trial, system configuration	152
	Data capture and processing	154
	Measurements	154
	Temperature changes	157
	Train transit effects	157
	The influence of the excavation of a new adjacent tunnel	158
	Conclusions	159
	Fibre-optic systems	160
7	Instrument systems for tunnelling projects	167
	Initial assessment (experience)	167
	Tunnelling and instrumentation	168
	Preliminary predictions	168
	Numerical assessment	177
	Instrumentation	183
	Field instrumentation layouts (ideal)	185
	Convergence	185
	Structures and deformations	187
	Global settlement at ground level	187
	Data presentation	194

8	Data logging, recovery and presentation	201
	<i>Basics</i>	201
	<i>Radio connection</i>	203
	<i>Mesh networks</i>	205
	<i>WiFi and IP address sensors</i>	205
	<i>Internet-based data presentation and underground construction information management systems (UCIMS)</i>	206
9	Conclusions	209
	<i>Notes</i>	211
	<i>References</i>	212
	<i>Index</i>	213

Figures and tables

2.1	Diagram of the concept of void ratio	7
2.2	Idealised column of soil experiencing one-dimensional consolidation	7
2.3	Normal consolidation for a clay soil on a $1 + e/\text{normal stress plot}$	8
2.4	Normal consolidation for a clay soil on a $1 + e/\log_e \text{ normal stress plot}$	8
2.5	Unloading (swelling) curves on a $1 + e/\text{normal stress plot}$	9
2.6	Equilibrium stresses on a rectangular element	10
2.7	'Mohr circle of stress' at failure	10
2.8	'Mohr circle of stress' for a drained material with cementing or cohesion	11
2.9	Deformation in the principal stress directions	11
2.10	Idealised grain contact	13
2.11	State boundary relationships for a clay on an elastic unloading line	13
2.12	The simplified ellipse form assumed in the Roscoe-Burland version in the CRISP program	15
2.13	Set of state boundary surfaces	15
2.14	Isometric view of the state boundary surface on $s', t, 1 + e$ axes	15
2.15	Simplified pore pressure measuring unit	16
2.16	Flushable modification to a piezometer	16
2.17	Schematic diagram of a pneumatic piezometer	17
2.18	Deformation of a diaphragm	17
2.19	Arrangement of a diaphragm	18
2.20	Simplified full Wheatstone bridge circuit	18
2.21	Suction gauge (after Imperial College, London)	19
2.22	The BAT piezometer system (courtesy Profound BV)	19
2.23	Undrained surface ($1 + e = \text{constant}$)	21
2.24	Detailed wall section	22
2.25	Locations of initial total stress for A to E	22
2.26	Magnified rotation of the wall due to excavation	23
2.27	Total stress paths A to E	23
2.28	Stress paths for element A	23
2.29	Stress paths for elements B and C	24
2.30	Changes in pore water pressure (pwp)/depth of excavation	25

2.31	Stress paths for elements D and E	26
2.32	Location of pore pressure measurement units in a cutting excavation	27
2.33	Total stress paths for typical piezometer locations	27
2.34	Decay of pore suction with swelling of the clay and fall of the critical-state strength	28
2.35	Locations of pore pressure measuring units for an embankment construction	29
2.36	Total effective stress paths for the D ₁ , D ₅ and D ₉ units	29
2.37	Typical piezometer layout around a trial tunnel (4 m to 10 m diameter) in over-consolidated clay	30
2.38	Initial stress conditions prior to tunnel construction in an over-consolidated clay	31
2.39	Total stress conditions after tunnelling	31
2.40	The development of over-consolidated stresses in geological time to give the stress conditions at points (C' and C) and (D' and D) in the original ground	32
2.41	Stress path for a crown element	32
2.42	Stress path for side element on the horizontal centre line	33
2.43	Pore pressure suction distribution round a tunnel construction	35
2.44	Contours of pore water pressure changes when Δt exceeds yield and rupture mechanisms begin to develop	35
2.45	Changes in pore water pressure with time assuming rapid continuous tunnelling	36
3.1	Hydraulic settlement unit	39
3.2	Comprehensive automatic hydraulic settlement system used inside structures (also known as a 'water level' system)	40
3.3	Piezometric settlement system	41
3.4	Pipework losses due to air bubbles	42
3.5	Line of electrolevel beams	43
3.6	Principle of resistance changes in an electrolevel	44
3.7	Wheatstone bridge for electrolevels	45
3.8	Fredericks Company 0711 series (five samples) electrolevel typical output	45
3.9	Tunnel section: non-alignment beam system	46
3.10	Limitation, unmeasured vertical displacement measurement on a vertical bar unit	47
3.11	Limitation, unmeasured axial displacement measurement in an angled bar unit	47
3.12	The influence of unknown displacements on the real position of pin C	48
3.13	Measured displacement vectors	48
3.14	Best-fit estimate of in-line length changes to match surveyed displacements of F	49
3.15	Location of reference pins and beams 1 to 16	49
3.16	Full settlement data for a continuous chain	50
3.17	Estimated settlements based on alternative tilt meter layouts	50

3.18	Schematic diagram of an inverted pendulum system	52
3.19	Principle of the optical pendulum reader system	52
3.20	Use of plate settlement units in an embankment construction	53
3.21	Rod extensometer settlement measurement	54
3.22	Rod extensometer systems showing fixities and manual versus electrical measurement	55
3.23	Reed switch unit	56
3.24	Magnetic field inside an inclinometer casing	57
3.25	Installation of a spider magnet system outside the inclinometer casing	58
3.26	Spider magnet and probe	59
3.27	Plate magnet	59
3.28	Physical layout of one inclinometer and an included settlement system (spider magnets)	60
3.29	Data available from a single inclinometer and settlement system	61
3.30	MEMS accelerometer (diagrammatic)	63
3.31	Complete inclinometer probe	63
3.32	Inclinometer casing/wheel alignment	63
3.33	Sprung wheel action	64
3.34	Forces on the sprung wheel pair	64
3.35	Sprung wheel action in distorted casing (diagrammatic)	64
3.36	Dimensions of a typical inclinometer probe	65
3.37	Inclinometer probe limitations within 70 mm outer diameter (OD) curved casing	65
3.38	Exaggerated diagram of curvature limits	65
3.39	Excessive deformation of casing preventing use of a standard inclinometer	66
3.40	Inclinometer casing groove nomenclature	67
3.41	Elimination of sensor/body errors using a double traverse	67
3.42	Typical inclinometer casing installation	70
3.43	Causes of changes in casing length (exaggerated)	71
3.44	Fixed inclinometer casing connection (top) and telescopic connection (bottom)	72
3.45	Inclinometer casing installed and grouted on an oversized borehole (exaggerated)	75
3.46	Very poorly grouted hole with grout voids shearing on slip zone through D	76
3.47	Inclinometer casing/grout relationship where the casing is on the side not being pushed	77
3.48	Simplified plastic flow of settlement round inclinometer casing (very unlikely)	77
3.49	Cutaway view of an in-place inclinometer reading unit	79
3.50	Chain of in-place inclinometers from the top of the borehole	79
3.51	HPGs in a road/railway embankment	81
3.52	HPG in a dam body	81
3.53	Inclinometers and horizontal profile systems in retaining wall construction	82

3.54	HPGs associated with compensation grouting during tunnel construction	83
3.55	Very simplified slip circular failure	84
3.56	Horizontal movement contours for an idealised circular slip (Figure 3.55)	85
3.57	Vertical movement contours for an idealised circular slip (Figure 3.55)	85
3.58	Realistic contours of horizontal displacement	86
3.59	Idealised deformed blocks for a cantilever retaining wall	87
3.60	Idealised horizontal displacement contours for a cantilever wall	87
3.61	Displacement points from three inclinometer/settlement systems	89
3.62	Displaced rectangular element from Figure 3.61	90
3.63	Four original triangular elements	90
3.64	Bodily displacement of the triangular element	91
3.65	Bodily rotation and shear distortion of a triangular element	92
3.66	Idealised shear stress and shear strains in a square element	92
3.67	Mohr circle of strain	93
3.68	Corresponding Mohr circle of stress	93
3.69	Nominal strain and shear within the triangle 3A–4A–4B when all body displacements are removed	94
3.70	Mohr circle of strain for the triangular elements	95
3.71	Mohr circle of strain identifying planes of potential failure	96
3.72	Shear deformation on failure planes	97
3.73	Elements available from a comprehensive array of inclinometer/settlement units (7 in number)	97
3.74	Complete set of data available from a comprehensive instrument system	98
3.75	Complete set of data available from a comprehensive instrument system	99
4.1	Components of a vibrating wire unit	100
4.2	Basic vibrating wire layout with flexing diaphragm at end B	102
4.3	Simplified section through a diaphragm unit measuring load or pressure changes at end B	103
4.4	Deflection of diaphragm. End B	103
4.5	Tensile large strain gauge	104
4.6	Compressive/tensile small strain gauge	104
4.7	Diaphragm under internal and external (applied) pressure	105
4.8	Section through a piezometer	106
4.9	Heavy-duty piezometer incorporating a vibrating wire insert	106
4.10	A spring-controlled vibrating wire instrument	107
4.11	Embedded concrete strain gauge	107
4.12	'Sister bar'	108
4.13	Section through part of a heavy-duty load cell	108
4.14	Diaphragm (oil-filled) pressure cell	110
4.15	Ideal linear strain measurements to determine the full two-dimensional field	112

4.16	Layout of vibrating wire pressure cells in a pit	112
4.17	Three-dimensional array	113
4.18	Three-dimensional stress measurement in soil	113
4.19	The Mohr circle of stress	114
4.20	The Mohr circle of strain	115
4.21	Orientation of a strain gauge rosette and the planes across which nominal strain acts giving rise to revised nomenclature of the strains	116
4.22	Typical load cell arrangement on a tension anchor	117
4.23	Progress of a Griffith's crack	118
4.24	Typical Georgian facade (brick/stucco faced) with inadequate brick foundations	119
4.25	Deformation between loaded columns	120
4.26	Inverted brick arches	120
4.27	Differential movements due to tunnelling	121
4.28	A simple tension crack monitor	122
4.29	Shear and tensile crack monitoring	123
4.30	Three-dimensional crack monitoring – example A	123
4.31	Three-dimensional crack monitoring – example B	124
4.32	An example of simple tension crack monitoring	124
4.33	An example of transverse and aligned displacement crack monitoring	125
4.34	An example of a three-dimensional crack meter	125
5.1	Typical modern 'total station' (courtesy Leica Geosystems)	127
5.2	Vertical section of a sight line	127
5.3	Plan of a sight line	128
5.4	Isometric drawing of the reference points	128
5.5	Plan view of the reference points	129
5.6	Isometric diagram of reciprocal sights from reference stations	129
5.7	Plan view of Figure 5.6	130
5.8	Correction for North reference angle	130
5.9	Inclusion of distance error band	131
5.10	Corrected northings and eastings of the ATS	131
5.11	The facade of St Pancras Station in London monitored as part of a new London Underground ticket hall excavation below it	132
5.12	Traditional tunnelling beneath a live railway track	133
5.13	Jack box tunnelling beneath a working station	134
5.14	Diagram of a reflecting prism	134
5.15	Cross-section through a triple prism	135
5.16	True and apparent recognition of prism centres	135
5.17	Prism showing the light path	136
5.18	Deviation of the axis in dependence of the misalignment	136
5.19	Typical prism in mount attached to a wall	137
5.20	A prism mounted on a pandrol clip	138
5.21	Track monitoring (note: track distortion exaggerated)	138
5.22	View from the ATS station of four arrays of reflections showing multiple prism interference	139

5.23	Diagrammatic representation of the reflected locations for a single sweep	141
5.24	Diagrammatic representation of the development of surfaces with multiple sweeps	142
5.25	The Faro Photon 120/20 laser scanner	143
6.1	Part of an installed BCS	145
6.2	Components of the BCS	145
6.3	BCS with bent long bar	146
6.4	Reference pin	146
6.5	Basic rotation and extension to P_2	146
6.6	Insertion of the cam C to P_1 - P_2	147
6.7	Action of BCS from P_2 to P'_2	148
6.8	Key angles for P_2 to P'_2	148
6.9	Displacements P_2 to P'_2	149
6.10	Rotation of the cam from P'_2 to P''_2	149
6.11	Displacement from P'_2 to P''_2	150
6.12	Summed displacement from P'_2 to P''_2	151
6.13	Completely closed BCS	152
6.14	An installed BCS system	153
6.15	An installed BCS system (detail view)	153
6.16	Data from a BCS system – cross-sectional plot of processed data	154
6.17	Data from a BCS system – normal vector displacements of an individual monitoring point	155
6.18	Data from a BCS system – extreme displacements of a lined rock tunnel subjected to an adjacent blast (on the right-hand-side)	155
6.19	Time movements of an individual monitoring point before, during and after the blast	156
6.20	The data from Figure 6.19 with the permanent offsets experienced during previous blasts added	156
6.21	Key locations of deformation in a tunnel approaching failure	158
6.22	The rate of crown movement with time	159
6.23	Sketch of a fibre-optic system	161
6.24	Etched pattern on the fibre-optic cable (diagrammatic)	161
6.25	Laser input/transmitted and reflected signals at one BRAGG	161
6.26	Response/frequency curve for a unique BRAGG	162
6.27	Frequency shift on a single BRAGG	162
6.28	Fibre-optic cables located on an inclinometer casing	163
6.29	Strain measured in the three BRAGGs	164
6.30	Diagrammatic representation of the bending strains round the tube (drawn inward (compression) from the inner perimeter)	164
6.31	Determination of the bending axis by linear strain distribution	165
6.32	Diagrammatic relationship between measured maximum strain E_{\max} and R	166
6.33	Diagrammatic illustration of unmeasured angle changes using fibre-optic strains	166
7.1	An idealised settlement trough	169
7.2	An idealised settlement trough	170

7.3	Simplified inverted error curve	171
7.4	Displacement vectors in the vicinity of tunnel construction	172
7.5	The relationship between trench width and depth of tunnel (clays)	172
7.6	The relationship between trench width and depth of tunnel (sands)	173
7.7	Variation of i below ground level for adjusting the settlement trough with depth	174
7.8	Boscardin and Cording damage assessment diagram	174
7.9	Trough distortion	175
7.10	Angular distortion versus horizontal location	175
7.11	Division of a tunnel into sectional blocks	176
7.12	Settlement conic for element 3	176
7.13	Assessment of component of horizontal strain	177
7.14	Equal area elements	178
7.15	Deformed mesh	180
7.16	Displacement vectors	180
7.17	Vertical displacements	181
7.18	Horizontal displacements	181
7.19	Zero extension directions (potential failure planes)	182
7.20	Finite element mesh for a wall/tunnel interaction problem	182
7.21	Shear strain data for a pile/tunnel interaction: (a) finite element analysis, (b) physical model	183
7.22	A digital tape extensometer	186
7.23	Typical tape extensometer monitoring array	186
7.24	The Mansion House, London, basement	188
7.25	Typical layout of inclinometers, settlement gauges and piezometers around a trial tunnel	189
7.26	Potential 45° inclined inclinometer layout	190
7.27	Survey levelling points at the Mansion House	190
7.28	Developing settlement trough at the Mansion House, approaching	191
7.29	Developing settlement trough at the Mansion House, at completion of tunnelling	191
7.30	Mansion House area global settlement as a three-dimensional plot	192
7.31	Contours of settlement inside the Mansion House	192
7.32	Idealised layout of part of a sensitive structure	193
7.33	Vertical electrolevel/MEMS beam	194
7.34	Idealised output for building data, level profile (raw data)	195
7.35	Settlement profile at t_N	196
7.36	Curvature profile (angle of distortion) at t_N	196
7.37	Change in angle of distortion at location 6 up to time t_N	197
7.38	Idealised angle of distortion (curvature)	197
7.39	and 40 Change in angle of distortion β with time and change in $\Delta\beta/\Delta t$ with time	198
7.41	Compensation grouting layout	199
7.42	Vertical section through the instrumentation array	199
8.1	A vibrating wire readout/recorder	202
8.2	Section through a typical high-quality instrumentation cable	203
8.3	Typical star network	204

8.4	Star network transmitter	204
8.5	Typical mesh network	205
8.6	Mesh network module	206
8.7	A typical screenshot from a web-based graphical package	207
8.8	A typical screenshot from a GIS UCIMS package	208

Table

7.1	Data ranges for the 'volume loss' typically experienced in tunnel monitoring	173
-----	--	-----