

# Materials for Advanced Ultra-supercritical Steam Turbines - Advanced Ultra-supercritical Component Demonstration

DOE Contract DE-FE0025064

**Robert Purgert**

purgert@energyinohio.org  
Principal Investigator  
Energy Industries of Ohio

**Horst Hack**

hhack@epri.com  
Presenter / Technical Manager  
Electric Power Research Institute

2019 NETL Annual Project Review Meeting  
for Crosscutting Research

April 9, 2019



# ComTest Project Objectives

- **Higher efficiency** for new and existing fossil fuel plants
  - 10% above today's new state-of-the-art coal power plants, and
  - 25% above that of the average power plants in the U.S. existing fleet
- **Lower emissions** (NO<sub>x</sub>, SO<sub>x</sub>, CO<sub>2</sub>)
- **Minimized risk** for utilities desiring to build A-USC plants
- Fabrication of **full scale components** (850 MWe) for 760°C
- Accelerated development of domestic **supply chain** for advanced materials and components (greenfield & retrofit)
- **Validation of technology** applicable to multiple fossil, nuclear, and renewable power generation options, all targeted by the U.S. DOE NETL Cross-Cutting Research Technology Program


# Strategic Alignment with DOE Fossil Energy Objectives

**Power Plant Efficiency Improvements** – Develop cost-effective, reliable technologies to improve the efficiency of new and existing coal-fired power plants.

- Project aims to close gaps to achieve readiness for commercial scale demonstration of Advanced Ultra-Supercritical (AUSC) technology
- Completion scheduled for September 2021
- Supports increase in power plant steam temperatures for higher cycle efficiency
  - Average efficiency of US coal-fired fleet = 33% HHV
  - A-USC plant efficiency over 45% HHV at 1,400°F (760°C) steam temperature


# Increasing Steam Conditions to Dramatically Improve Efficiency

Plant Efficiency (HHV) as a Function of Steam Temperature




# Materials Limit the Current Technology

Today's State-of-the-Art (USC) Coal-Fired Power Plants are defined by steel technology



# ComTest Project Status




- ComTest is a \$27M DOE-funded project
- Phase 1, which began in November 2015, served to identify the technology gaps, as well as the scope and cost of required testing
- Phase 2, which was awarded in December 2018, will perform an advanced manufacturing effort to complete US-based supply chain development for full commercial scale (800-850 MWe) A-USC components made of nickel-based alloys, components operating at up to 760°C.

**Close gaps to achieve readiness for commercial scale demonstration**



# AUSC Commercialization Roadmap

Technology Readiness Levels			Roadmap to AUSC Demo		
2000	2005	2010	2015	2020	2025
Materials Evaluation (Nickel Superalloy Focus)	Component Mockup	Steam Loop at Plant Barry. Large forgings & castings	AUSC Component Test (ComTest)	AUSC Demonstration	
Laboratory TRL 2-3	Proof of concept TRL 4	Component Test TRL 4-5	System TRL 4-7	Overall TRL 8-9	



Recently completed DOE-sponsored projects achieved TRL = 4/5  
 AUSC ComTest will achieve TRL = 7 (ready for full scale demo)

# ComTest Phase I - Key Accomplishments

- Evaluated multiple potential host sites for test facility
- Identified viable host sites (Ohio and Alabama)
- Completed Pre-FEED and FEED tasks
- Optimized project scope – Closed budget gap
- Prepared preliminary capital cost estimates
- Worked with suppliers to develop supply chain
- Determined that operational testing of the steam turbine and the A-USC superheater were not required
- Revised scope of Phase II to focus on full-scale component manufacturing capability readiness
- Completed Detailed Engineering effort for revised Phase II scope



# ComTest Phase II will achieve...

- Closing of the remaining gaps and reducing the risks for manufacturing components from advanced materials for commercial demonstration
- Fabrication of full-scale versions of selected key components made of nickel-based alloys
- Validation of a qualified supply chain, to provide greater cost certainty for components
- Obtaining American Society of Mechanical Engineers (ASME) code approval for new materials, components and processes

## Additional benefit:


- Manufacturing technology will be applicable to other advanced fossil energy high temperature cycles

Designed to close the remaining gaps to implement A-USC technology

# ComTest Phase II Participant Map



# ComTest Phase II – Project Organization Chart



# ComTest Phase II Work Plan



- Fabrication of components identified as being outside of the proven capabilities of the existing supply chain, including:
  - Steam turbine rotor forging and Haynes 282 nozzle carrier casting
  - Superheater and reheater header and tube assemblies
  - Large diameter pipe extrusions and forgings
  - Test valve articles to support ASME Code approval
- Key fabrication steps will also be done including boiler weld overlays and simulated field repairs
- Extensive inspection and quality assurance testing of the components
- ASME Code approval for key components

**Significant fabrication work will be done with lessons learned provided**

# ComTest Phase II – Statement of Project Objectives

**Task 1** – Project management and planning

**Task 7** – Procure the AUSC materials that will be fabricated into AUSC components and sub-assemblies in Tasks 8 through 10.

**Task 8** – Fabricate AUSC boiler and superheater components and sub-assemblies.

**Task 9** – Fabricate a cast nickel-based steam turbine nozzle carrier casing (Haynes 282).

**Task 10** – Fabricate forged nickel-based components for an AUSC steam turbine (Haynes 282) and for an AUSC main and reheat steam piping system Inconel 740).

**Task 11** – Conduct testing and obtain ASME Code Stamp approval for nickel-based pressure relief valve designs that would be used in AUSC power plants up to approximately 800 MWe size.

**Task 12** – Develop a testing matrix for more extensive mechanical testing and metallurgical examination of the fabricated components fabricated in Tasks 8, 9, and 10.




# ComTest Schedule

- **Phase I**

- Pre-FEED
- NEPA
- FEED
- Detailed Engineering

- **Phase II**

- Negotiations, Sub-awards & POs
- Turbine Rotor Forging
- Nozzle Carrier Casting
- Valve Testing / NB Qualification
- Superheater Component Fab.
- Pipe Forgings and tube trials
- Metallurgical Testing Plan
- Evaluation & Reporting



Based upon January 7, 2019  
 Project Management Plan

# ComTest Phase II – Work Scope – Key Areas

Item	Scope of Work
Boiler / Superheater	Build 800-MWe sized nickel-based alloy parts of superheater and steam piping system – steam headers, boiler tube assemblies, tube membrane panels and weld overlays, large diameter, thick-wall pipe and fittings (up to 25 inch OD x 4 inch thick wall). Field erection and repair simulation.
Nickel-based Alloy Valves	National Board qualification of a scale spring-loaded and power actuated pressure relief valve (PRV/PARV) design for conditions up to 760°C / 345 bar
ASME Code Cases	Alternate pressure-relief method, flanged fittings, shielded metal-arc welding
Steam Turbine	Fabricate commercial-scale nozzle carrier casing (10 tons) and rotor disk forging (20 tons) – both from Haynes 282


# Advanced Materials in ComTest Phase II

- Grade 91/92 – membrane panels
- Haynes 282 – tubes, castings, forgings
- HR6W – tubes, pipe/header
- Inconel 617 – safe ends on HR6W tubing
- Inconel 740H – tubes, pipes, forgings
- Sanicro 25 – tubes
- SAVE12AD – pipe/header
- TP347H and Super 304H – lower temperature zones




Applicable to multiple high-temperature advanced generation options

# Boiler and Steam Piping Scope for Phase I

- Fabricate A-USC boiler and superheater components and sub-assemblies, membrane panels, SH/RH tubes, headers, pipes
- Bend thick wall large diameter Inconel 740 pipe
- Fabricate forged Inconel 740 wye fitting
- Field erection and repair simulation
  - Waterwall panel butt welds and longitudinal seam welds
  - Inconel 740H thick wall piping –circumferential welds of fittings and plugs
  - Grade 92 tube membrane panel repair –simulated “Dutchman” repair
  - Evaluation of strength of post-weld-heat-treatment (PWHT) vs non-PWHT welds in 740H
  - Determine ability to weld repair and to use innovative repair options such as weld overlays





# Steam Turbine Assembly – Nozzle Carrier





# A-USC Steam Turbine Nozzle Carrier Casting (10 tons Haynes 282)

Note: Trial casting is half of lower section




# Steam Turbine Rotor Forging in Phase II

- Rotor Forging (Haynes alloy 282)
  - Previous work with 24" diameter triple melt ingot to make 5,000 lb. pancake to simulate disk for bolted rotor turbine design
  - GE's new welded rotor design uses a much larger shaft forging
    - Requires 36" diameter, 30,000 lb. triple melt ingot (largest possible)
    - Concern for ingot segregation and cracking
    - Challenge to achieve fine grain in forging, sonic test capability in doubt



Alloy 282 pancake forged at Wyman-Gordon



Proposed Phase II rotor forging

# ASME Code Case Development for Phase II

- Alternative overpressure protection method vs. spring activated PRV at the superheater outlet
- Expand ASME B16.34 to allow bolted flange design at high temperatures
- Revision of Code Case 2902 for Inconel 740H, to permit the use of shielded metal arc welding (SMAW) process
- Qualification of high temperature PRV design
- Parallel Code Case work (testing separately funded)
  - Code case for wrought H282
    - GE submitted the request to ASME with support by Haynes International
  - Mechanical properties data of Thermanit 263 weld filler wire
    - Add SMAW to ASME Code Case 2902

# ComTest Phase II – Expected Key Outcomes

Task Areas	Key Outcomes
<b>Fabrication of Boiler Components</b>	<ul style="list-style-type: none"><li>• Ability to complete fabrication of superheater/reheater assembly, using accepted shop methods (machining, bending and welding)</li><li>• Verification that weld overlay may be applied to membrane panels</li></ul>
<b>Fabrication of Turbine Casting</b>	<ul style="list-style-type: none"><li>• Ability to produce nozzle carrier casting that meets specified OEM requirements</li><li>• Verification that valid repair methods are available</li></ul>
<b>Fabrication of Forged Components</b>	<ul style="list-style-type: none"><li>• Ability to produce steam turbine rotor forging that meets specified OEM requirements</li><li>• Verification that valid repair methods are available</li></ul>
<b>Pressure Relief Valve (PRV) Qualification</b>	<ul style="list-style-type: none"><li>• Production of test valve component</li><li>• Completion of National Board qualification test</li><li>• Acceptance of valve qualification by ASME for high-temperature PRV valve designs</li></ul>

# ComTest Phase II – Current Status and Progress

- ComTest Phase II was awarded by DOE on December 12, 2018
- Submitted Phase I Topical Report
- Completed updated Project Management Plan
- Received vendor input for Risk Management Plan
- Executed key subcontracts
  - Riley
  - GE / Alstom Power
  - EPRI
- Conducted Phase II kickoff meeting with DOE on March 4, 2019
- Planned quarterly meeting for April 10, 2019
  - Co-located with NETL Crosscutting Review meeting (Pittsburgh, PA)



# Conclusions

- Identified Phase II project scope to close gaps, to achieve readiness for commercial scale demonstration of AUSC technology
- Focus on full-scale manufacturing technology and supply chain development for advanced materials yields crosscutting benefits:
  - Supercritical CO<sub>2</sub> cycles
  - Concentrated solar
  - Nuclear
  - Enhanced flexible operation – even at lower temperatures
- Supports efficiency and flexibility improvements for new and existing generation units

# ComTest Support Acknowledgement

*Acknowledgment: This material is based upon work supported by the Department of Energy under Award Number DE-FE0025064 and the Ohio Development Services Agency under Grant Agreement Number CDO-D-15-01.*

*Disclaimer: This report was prepared as an account of work sponsored by an agency of the United States Government and an agency of the state of Ohio. Neither the United States Government nor any agency thereof, nor any of their employees, nor the state of Ohio nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or by the state of Ohio or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof or the state of Ohio or any agency thereof.*

# Together...Shaping the Future of Electricity